DRIVEWAY PERMIT



Code Enforcement/Building/Zoning

401 S. Main Street, Hatfield, PA 19440
O: (215) 855-0781x108 F: (215) 855-2075
Code@HatfieldBorough.com

<u>Code@HatfieldBorough.com</u> <u>www.HatfieldBorough.com</u>

DRIVEWAY PERMIT APPLICATION

		DICTULATION	ERMIT ATTECATION						
			construction documents. Commercial plans shall b						
signed/sealed by a	design professio	onal. Residential plans may have to b	be signed and sealed, depending on the complexity must include a copy of the current property surv	of Date _/	_/				
tile project. Perinit a		learly showing all existing and propo		^{ey,} Fee \$					
		PROPER	TY INFORMATION						
Number		Street							
OWNER INFORMATION									
First Name	Las	st Name	Daytim	e Phone					
E Add			Call Di-						
Email Address	i		Cell Pho	me					
Number	Str	eet	City/Zip	City/7in					
Street			5.677 =	G(7) 2.1p					
		CONTRAC	TOR INFORMATION						
			ing completed by the Property Owner						
License #	Name	Address	Phone	/Email	Value				
		ENCINE	ER INFORMATION						
License #	l Na	ime Address	Phone/Ema	i l 	Value				
			- -						
	I			I	I				
Existing Length	by Width		Proposed Length by Width						
Road Driveway	Abuts		Does Curbing Exist						
Minimum Curb	Radius		Maximum Curb Radius						
Dropocod Curfo									
			Time of Proposed Work						
Dip Section Pip	e and Const	ruction Sizes and Types	A DRIVEWAY CHANGE						
ΔΡΡΙ	TCATTON		DO DRIVEWAY CHANGE S NOT GRANT APPROVAL TO	START W	ORK				
			nd ordinances and with the conditions of		i				
		• •	y, express or implied, on Hatfield Bor	•					
			ork is not started in six (6) months, no	-					
		• •	ths in the judgement of the Borough.	_					
I =			nter the premises for which this perm	_					
			pect the proposed work. Failure to co	nply with the	above will				
result in a STO	r WURK UF	NUEK.							
Owne	r Authorize	ed Name	Owner/Authorized Signature		Date				

DRIVEWAY PERMIT

SITE PLAN

lowing information on	the plan.		
Property dimensions			
	ks/patios, sheds, pools	s, fences and driveways with dimension	ons
All proposed construction	n with dimensions		
Distances from all pro	perty lines to propos	sed construction	
Distances between existi	ng buildings and propo	sed construction	
e Plan or Plot Plan use	t in place of this par	ge JO Additional pages inclu	uded with Annlication
		D BOROUGH USE ONLY	<u>чесе ини аррисации</u>
Zoning Permit Fee	\$	I PA State Act 13 Fee	\$4.50
		TOTAL OF ALL FEES	
Application Fee	\$150.00	IOIAL OF ALL FEES	\$

HATFIELD BOROUGH

DRIVEWAY PERMIT

DRIVEWAY PERMIT INFORMATION

After the Driveway Permit Application is submitted and the initial \$150 permit fee is paid, the Driveway Permit Application is reviewed by the Borough Engineer. This may take several days to a couple weeks. The Borough Engineer, at his convenience, may schedule to meet the applicant at the site of the application. The applicant or a representative of the applicant would have to meet the Borough Engineer at the proposed driveway site in case there are any questions on the submitted Driveway Permit Application. The Borough Engineer will reach out to the applicant if the need for a site visit is required.

After inspecting the proposed driveway site, the Borough Engineer may determine that additional conditions may be needed, which will then be added to the Driveway Permit Application. Several days to a couple weeks shall be allowed for processing of the application.


The Zoning Department will contact the applicant when the Permit has been processed, and is ready to be paid for and picked up. There will be additional Permit Fees based on the size of the driveway extension.


Submitted with the Driveway Permit Application should be any documents and drawings that show the outlines of the property and it's existing conditions included but not limited to driveways, walkways, drains and culverts, the proposed changes including any driveways, walkways, drains or culverts, and the relationship of the property and the proposed changes to the Borough Street.

The Driveway Permit is good for one (1) year after the date of issuance. If an extension is needed, the Borough must be notified in writing.

GENERAL REGULATIONS

- 1. Paved driveways shall consist of 2" depth bituminous wearing course on 4" depth 2A modified stone base.
- 2. The property owner is responsible for obtaining any other permits which may be required and complying with any other State or Federal Government regulations.
- 3. The slope of the driveway shall not exceed twelve (12) percent. The first twenty feet from the curbline shall not exceed five (5) percent.
- 4. A driveway serving a single dwelling unit shall have a minimum width of ten (10) feet. A common driveway, serving up to four (4) dwelling units shall have a minimum width of sixteen (16) feet.
- 5. A driveway serving a single dwelling unit shall be located as far from street intersections as reasonably possible, but no less than fifty (50) feet from the nearest street intersection.
- 6. The construction of all driveways will be subject to the inspection and approval of the Borough. The Borough shall be notified a minimum of forty-eight (48) hours in advance of construction.
- 7. Concrete aprons for driveways shall be six (6) inches thick and reinforced with six (6) by six (6) inch number nine (9) wire. The wire shall be installed no closer than 1/2 inch from the top or bottom surfaces of the apron.
- 8. Curbing
- a) The permit may require the installation of curbing wherever it is required to control access and/or drainage. All curbing must be permanent curbing.
- b) Where property abutting the road right of way line could be used as a parking area, the permit may require curbing, permanent guiderail or fencing to be constructed along the right of way line in order to prohibit vehicle encroachment upon the sidewalk or shoulder area
- c) When curb exists adjacent to the proposed driveway, the line and grade of the existing curb shall be matched, unless otherwise authorized by the permit.






NOTES:


1. IF CURB IS BEING REPLACED, MATCH HEIGHT OF EXISTING CURB ON EACH END.

HATFIELD BOROUGH CONCRETE CURB DETAIL

NO SCALE



HATFIELD BOROUGH STRAIGHT CURB & SIDEWALK DETAIL NO SCALE




4" AIR-ENTRAINED CONCRETE (MIN. 4,000 PSI) 4" AASHTO #57 STONE


SIDEWALK DETAIL NOTES:

- SIDEWALKS AT DRIVEWAYS SHALL BE 6" THICK CONCRETE WITH 6"x6" - NO. 9 WIRE (2 LAYERS, 2" APART. i" FROM SURFACE.)
- 0. 4" BIT. EXP. JOINT AT 20' O.C.
- 3 CONSTRUCTION JOINT AT 5' O.C.


HATFIELD BOROUGH SIDEWALK/DRIVEWAY APRON DETAIL

NO SCALE









HATFIELD BOROUGH TYPICAL DRIVEWAY PAVING DETAIL NO SCALE